

PROYECTO : RECONSTRUCCION DE TRAMO DE BORDO Y OBRA DE
PROTECCION EN MARGEN IZQUIERDA DEL RIO CHAMELECON , SECTOR EL
ZAPOTE.

JURISDICCION DE LA LIMA, DEPTO. DE CORTES

TALUDES:2:1

CORONA: 3.00 mts

EST.	Rasante	AREA	VOLUMEN	VOL. ACUM.
KMS		M2	M3	M3
0+000.000	100.00	2.64	0.00	0.00
0+010.000	100.00	2.26	24.49	24.49
0+020.000	100.00	2.48	23.71	48.21
0+021.255	100.00	4.32	4.27	52.48
0+030.000	100.00	14.12	80.63	133.10
0+040.000	100.00	25.78	199.51	332.61
0+044.000	100.00	31.80	115.16	447.77
0+050.000	100.00	36.71	205.53	653.30
0+060.000	100.00	45.49	411.01	1,064.31
0+070.000	100.00	54.94	502.16	1,566.47
0+073.680	100.00	57.66	207.19	1,773.65
0+080.000	100.00	61.52	376.59	2,150.24
0+084.470	100.00	63.61	279.67	2,429.91
0+090.000	100.00	62.93	349.87	2,779.78
0+100.000	100.00	60.62	617.75	3,397.53
0+107.560	100.00	56.73	443.58	3,841.11
0+110.000	100.00	52.17	132.85	3,973.96
0+120.000	100.00	38.49	453.29	4,427.25
0+128.600	100.00	29.91	294.09	4,721.34
0+130.000	100.00	29.63	41.67	4,763.01
0+140.000	100.00	26.63	281.27	5,044.28
0+150.000	100.00	29.57	280.99	5,325.28
0+151.300	100.00	30.98	39.36	5,364.63
0+160.000	100.00	29.05	261.11	5,625.75
0+170.000	100.00	22.67	258.58	5,884.33
0+173.570	100.00	19.50	75.26	5,959.59
0+180.000	100.00	15.30	111.86	6,071.45
0+190.000	100.00	3.68	94.87	6,166.32
0+193.519	100.00	2.23	10.40	6,176.72
0+200.000	100.00	2.04	13.86	6,190.58
0+210.000	100.00	3.92	29.83	6,220.41
0+213.000	100.00	2.46	9.60	6,230.00
VOL. BORDO =			6,230.00	M3