

PROYECTO : RECONSTRUCCION DE TRAMO DE BORDO Y OBRA DE PROTECCION
EN MARGEN IZQUIERDA DEL RIO CHAMELECON , SECTOR EL ZAPOTE.

JURISDICCION DE LA LIMA, DEPTO. DE CORTES

escollera de piedra el zapote

EST.	AREA	VOL.	VOL. ACUM.
KMS	M2	M3	M3
0+00.00	35.83	0.00	0
0+010.00	36.80	363.15	363.15
0+020.00	28.30	325.50	688.65
0+030.00	28.66	284.80	973.45
0+040.00	30.78	297.18	1,270.63
0+048.77	28.97	261.98	1,532.61
0+050.00	30.49	36.57	1,569.17
0+060.00	36.99	337.40	1,906.57
0+070.00	34.89	359.40	2,265.97
0+072.18	33.02	74.02	2,340.00
VOL. ROCA =		2,340.00	M3