

PROYECTO : CANALIZACION Y CIERRE DE BOQUETES , EN QUEBRADA CHINDONGO.

Jurisdiccion de el Progreso, Depto. De Yoro

TALUDES 2:1

PANTILLA DE CANAL= 11.00 MTS

EST. KMS	ELEVACIONES			AREA	VOL.	VOL. ACUM.
	T.N.	INV.	ALT.	M2	M3	M3
0+00.00	95.35	94.00	1.35	16.08	0.00	0
0+020.00	95.73	94.08	1.65	26.88	429.57	429.57
0+040.00	93.74	94.17	-0.42	5.13	320.14	749.71
0+060.00	94.99	94.25	0.74	7.68	128.10	877.81
0+070.00	93.63	94.29	-0.66	10.17	89.21	967.02
0+080.00	93.84	94.33	-0.49	9.12	96.42	1,063.44
0+100.00	95.29	94.41	0.87	13.54	226.60	1,290.04
0+120.00	94.89	94.49	0.40	17.72	312.63	1,602.67
0+125.37	95.89	94.52	1.38	22.39	107.70	1,710.37
0+140.00	95.86	94.58	1.28	11.21	245.79	1,956.16
0+160.00	95.84	94.66	1.18	20.33	315.42	2,271.58
0+180.00	95.92	94.74	1.18	20.72	410.53	2,682.11
0+198.77	95.99	94.82	1.17	14.06	326.46	3,008.57
0+200.00	96.00	94.82	1.17	16.50	18.79	3,027.36
0+220.00	96.11	94.91	1.21	19.00	354.99	3,382.35
0+240.00	95.61	94.99	0.62	6.23	252.34	3,634.69
0+260.00	95.99	95.07	0.92	11.96	181.93	3,816.62
0+280.00	96.36	95.15	1.21	15.70	276.58	4,093.20
0+300.00	96.50	95.24	1.26	17.85	335.43	4,428.63
0+320.00	96.68	95.32	1.36	18.32	361.62	4,790.25
0+340.00	96.80	95.40	1.40	18.95	372.65	5,162.90
0+360.00	96.89	95.48	1.40	19.17	381.22	5,544.12
0+380.00	97.12	95.57	1.55	21.66	408.33	5,952.45
0+381.12	97.13	95.57	1.56	21.78	24.41	5,976.86
0+400.00	97.21	95.65	1.56	22.07	413.87	6,390.73
0+420.00	97.09	95.73	1.36	18.09	401.62	6,792.35
0+440.00	96.93	95.81	1.12	14.33	324.23	7,116.58
0+456.02	96.99	95.88	1.11	14.13	227.87	7,344.45
0+460.00	97.03	95.89	1.13	14.32	56.67	7,401.12
0+480.00	97.14	95.98	1.16	14.83	291.55	7,692.67
0+500.00	97.22	96.06	1.16	16.95	317.86	8,010.53
0+520.00	97.32	96.14	1.18	17.21	341.65	8,352.18
0+540.00	97.42	96.22	1.20	17.44	346.52	8,698.70
0+560.00	97.52	96.31	1.22	17.74	351.78	9,050.48
0+580.00	97.59	96.39	1.21	17.79	355.30	9,405.78
0+600.00	97.69	96.47	1.22	18.31	361.06	9,766.84
0+620.00	97.82	96.55	1.27	20.67	389.84	10,156.68
0+640.00	98.79	96.64	2.16	20.73	413.97	10,570.65
0+660.00	98.47	96.72	1.75	16.47	372.00	10,942.65
0+680.00	97.95	96.80	1.15	18.55	350.27	11,292.92
0+700.00	98.19	96.89	1.30	19.95	385.04	11,677.96
0+720.00	98.39	96.98	1.41	21.61	415.61	12,093.57

PROYECTO : CANALIZACION Y CIERRE DE BOQUETES , EN QUEBRADA CHINDONGO.

Jurisdiccion de el Progreso, Depto. De Yoro

TALUDES 2:1

PANTILLA DE CANAL= 11.00 MTS

EST. KMS	ELEVACIONES			AREA	VOL.	VOL. ACUM.
	T.N.	INV.	ALT.	M2	M3	M3
0+740.00	98.47	97.07	1.40	21.63	432.36	12,525.93
0+760.00	98.58	97.16	1.42	22.40	440.21	12,966.14
0+780.00	98.81	97.25	1.56	24.93	473.24	13,439.38
0+800.00	98.99	97.34	1.65	26.78	517.09	13,956.47
0+820.00	99.14	97.43	1.71	27.67	544.54	14,501.01
0+840.00	99.32	97.52	1.80	29.22	568.91	15,069.92
0+860.00	99.54	97.61	1.93	31.75	609.63	15,679.55
0+880.00	99.70	97.70	2.00	32.86	646.03	16,325.58
0+900.00	99.81	97.79	2.02	32.97	658.23	16,983.81
0+920.00	100.01	97.88	2.13	34.84	678.06	17,661.87
0+940.00	100.31	97.97	2.34	38.32	731.61	18,393.48
0+960.00	100.43	98.06	2.37	39.51	778.31	19,171.79
0+960.19	100.43	98.06	2.37	39.51	7.51	19,179.29
0+980.00	100.55	98.15	2.40	37.98	767.50	19,946.79
1+000.00	100.63	98.24	2.39	37.98	759.61	20,706.40
1+020.00	100.67	98.33	2.34	38.84	768.19	21,474.59
1+040.00	100.76	98.42	2.34	38.95	777.85	22,252.44
1+060.00	100.86	98.51	2.35	37.70	766.45	23,018.89
1+080.00	101.00	98.60	2.40	40.67	783.65	23,802.54
1+100.00	101.15	98.69	2.46	37.25	779.16	24,581.70
1+120.00	100.91	98.78	2.13	38.20	754.49	25,336.19
1+140.00	101.21	98.87	2.34	37.95	761.46	26,097.65
1+160.00	101.53	98.96	2.57	49.21	871.59	26,969.24
1+180.00	101.47	99.05	2.42	44.83	940.41	27,909.65
1+200.00	101.98	99.14	2.84	54.65	994.79	28,904.44
1+207.08	102.09	99.17	2.92	52.73	380.13	29,284.57
1+220.00	101.19	99.23	1.96	40.96	605.26	29,889.82
1+240.00	101.60	99.32	2.28	38.04	790.07	30,679.89
1+260.00	101.28	99.41	1.87	38.58	766.19	31,446.08
1+280.00	101.36	99.50	1.86	35.99	745.62	32,191.70
1+300.00	101.79	99.69	2.10	38.23	742.16	32,933.86
1+320.00	102.21	99.89	2.32	36.12	743.47	33,677.33
1+340.00	102.06	100.08	1.98	34.62	707.37	34,384.70
1+360.00	102.48	100.28	2.21	41.22	758.39	35,143.09
1+360.84	102.50	100.29	2.21	35.37	32.17	35,175.26
1+380.00	102.72	100.47	2.25	37.04	693.68	35,868.94
1+400.00	102.58	100.67	1.91	30.46	674.96	36,543.90
1+420.00	103.62	100.86	2.76	49.01	794.70	37,338.60
1+439.90	102.79	101.05	1.73	25.77	744.03	38,082.63
1+440.00	102.78	101.05	1.73	25.68	2.57	38,085.20
1+460.00	102.35	101.25	1.10	22.44	481.24	38,566.44
1+480.00	102.34	101.44	0.90	21.70	441.42	39,007.86

PROYECTO : CANALIZACION Y CIERRE DE BOQUETES , EN QUEBRADA CHINDONGO.

Jurisdiccion de el Progreso, Depto. De Yoro

TALUDES 2:1

PANTILLA DE CANAL= 11.00 MTS

EST. KMS	ELEVACIONES			AREA	VOL.	VOL. ACUM.
	T.N.	INV.	ALT.	M2	M3	M3
1+484.01	102.34	101.48	0.85	19.21	82.03	39,089.90
1+500.00	103.19	101.64	1.56	21.72	327.28	39,417.17
1+520.00	103.31	101.83	1.48	26.75	484.72	39,901.89
1+540.00	103.64	102.02	1.61	23.39	501.43	40,403.32
1+560.00	103.58	102.22	1.36	17.49	408.87	40,812.19
1+575.50	103.41	102.37	1.04	19.81	289.10	41,101.29
1+580.00	103.36	102.41	0.94	17.95	84.96	41,186.25
1+589.00	102.52	102.50	0.02	7.77	115.75	41,302.00
Volumen de Corte =					41,302.00	m3
Volumen de Relleno =					2,120	m3