

PROYECTO : CANALIZACION Y CIERRE DE BOQUETES , EN QUEBRADA CHINDONGO.

VOLUMEN DE BORDO M.D.

Jurisdiccion de el Progreso, Depto. De Yoro

TALUDES 2:1

CORONA DE BORDO= 3.00 MTS

EST. KMS	ELEVACIONES			AREA M2	VOL. M3	VOL. ACUM. M3
	T.N.	RAS.	ALT.			
0+020.00	99.42	99.00	0.42	0.00	0.00	0
0+030.00	97.67	99.00	1.33	11.19	55.97	55.97
0+040.00	96.85	99.00	2.16	20.92	160.54	216.51
0+050.00	96.22	99.00	2.78	27.61	242.63	459.13
0+060.00	95.70	99.00	3.30	35.48	315.47	774.60
0+070.00	95.11	99.00	3.89	43.27	393.77	1,168.36
0+074.68	94.80	99.00	4.20	43.58	203.23	1,371.59
0+080.00	96.51	99.00	2.49	32.26	201.73	1,573.32
0+090.00	97.09	99.00	1.91	25.13	286.95	1,860.27
0+097.60	97.54	99.00	1.46	25.08	190.71	2,050.97
0+100.00	97.35	99.00	1.65	28.52	64.42	2,115.40
0+110.00	97.35	99.00	1.65	25.79	271.51	2,386.90
0+120.00	97.27	99.00	1.74	36.24	310.14	2,697.04
0+130.00	95.75	99.00	3.25	57.75	469.96	3,167.00
Volumen de Relleno =					3,167.00	m3