

BOQUETE No. 1

TALUDE IZQ. : 2:1

CORONA: 4.00

TALUDE DER. 2:1

EST.	MATERIAL DEL SITIO		MATERIAL ACARREADO		VOLUMEN DE RELLENO TOTAL		
	AREA	VOLUMEN	AREA	VOLUMEN	AREA	VOLUMEN	VOLUMEN
KMS	M2	M3	M2	M3	M2	M3	ACUMULADO
0+00.00	31.84	0.00	3.17	0.00	35.01	0.00	0.00
0+017.93	49.89	732.73	12.41	139.65	62.30	872.39	872.39
0+020.00	55.41	108.98	21.10	34.68	76.50	143.66	1,016.05
0+030.00	32.27	438.39	51.69	363.92	83.96	802.32	1,818.36
0+040.00	41.43	368.54	36.82	442.53	78.25	811.07	2,629.44
0+050.00	66.40	539.15	6.11	214.65	72.51	753.80	3,383.23
0+058.00	59.40	503.20	4.28	41.57	63.69	544.77	3,928.00

2,691.00

1,237.00

3,928.00

**PROYECTO : CIERRE DE BOQUETES EN BORDO DE MARGEN DERECHA, RIO BLANCO,
SECTOR CAMPO BLANCO.**

BOQUETE No. 2

TALUDE IZQ. : 2:1

CORONA: 4.00

TALUDE DER. 2:1

EST.	MATERIAL DEL SITIO		MATERIAL ACARREADO		VOLUMEN DE RELLENO TOTAL		
	AREA	VOLUMEN	AREA	VOLUMEN	AREA	VOLUMEN	VOLUMEN
KMS	M2	M3	M2	M3	M2	M3	ACUMULADO
0+00.00	5.34	0.00	1.17	0.00	6.51	0.00	0.00
0+010.00	12.44	88.90	5.14	31.55	17.58	120.45	120.45
0+020.00	23.14	177.91	8.21	66.74	31.35	244.65	365.10
0+026.15	27.12	154.56	13.93	68.07	41.05	222.63	587.73
0+030.00	23.63	97.70	26.54	77.90	50.17	175.60	763.33
0+040.00	23.63	236.32	37.93	322.34	61.56	558.65	1,321.98
0+042.14	25.89	52.99	40.48	83.90	66.37	136.89	1,458.86
0+060.00	29.58	495.32	47.31	783.99	76.89	1,279.31	2,738.18
0+070.00	24.38	269.78	40.60	439.57	64.98	709.35	3,447.53
0+080.00	20.03	222.06	24.36	324.79	44.39	546.85	3,994.38
0+090.00	10.35	151.91	8.51	164.34	18.86	316.25	4,310.62
0+096.00	38.50	146.55	1.10	28.83	39.60	175.38	4,486.00
		2,094.00		2,392.00		4,486.00	