

RECONSTRUCCION DE BORDO DE OBRAS DE
MARGEN DERECHA DEL RIO BLANCO,
TRAMO 2, SECTOR CAMPO OLIVO - BEJUCO

JURISDICCION DE POTRERILLOS
RELLENO DE PIEDRA

EST.	AREA	VOLUMEN	VOL. ACUM
KMS	M2	M3	M3
0+00.00	10.93	0.00	0.00
0+010.00	11.08	110.08	110.08
0+020.00	15.14	131.09	241.17
0+029.67	17.90	159.72	400.88
0+030.00	24.32	6.96	407.85
0+039.59	35.63	287.46	695.31
0+040.00	29.99	13.45	708.76
0+050.00	32.30	311.46	1,020.22
0+059.31	33.18	304.83	1,325.05
0+060.00	35.98	23.86	1,348.91
0+070.00	24.16	300.70	1,649.61
0+080.00	14.50	193.28	1,842.89
0+090.00	28.27	213.81	2,056.70
0+100.00	13.85	210.56	2,267.27
0+102.00	6.20	20.05	2,287.32
0+103.00	3.59	4.90	2,292.21
0+104.85	1.59	4.79	2,297.00

PIEDRA	2,297.00	M3
--------	----------	----

GEOTEXTIL	180.00	M2
-----------	--------	----

MATERIAL SELECTO Y SUELO CEMENTO	49.00	M3
-------------------------------------	-------	----

BORDO
TALUDES : 2:1 CORONA: 4.00 MTS

SUELO CEMENTO

EST.	AREA	VOLUMEN	VOL. ACUM
KMS	M2	M3	M3
0+040.00	0.00	0.00	0.00
0+050.00	0.80	3.99	3.99
0+059.31	1.00	8.37	12.36
0+060.00	1.00	0.69	13.05
0+070.00	1.19	10.95	24.00

RELLENO ETRE ROCAS

EST.	AREA	VOLUMEN	VOL. ACUM
KMS	M2	M3	M3
0+040.00	0.00	0.00	0.00
0+050.00	0.86	4.30	4.30
0+059.31	1.01	8.70	13.00
0+060.00	1.03	0.70	13.70
0+070.00	1.23	11.30	25.00

BORDO EXISTENTE, MATERIAL DEL SITIO

EST.	AREA	VOLUMEN	VOL. ACUM
KMS	M2	M3	M3
0+040.00	0.00	0.00	0.00
0+050.00	14.02	70.11	70.11
0+059.31	26.02	186.39	256.50
0+060.00	26.00	17.95	274.44
0+070.00	18.86	224.28	498.72
0+080.00	50.00	344.28	843.00

MAT. DEL SITIO	843.00	M3
----------------	--------	----

MAT. ACARREADO	1,213.00	M3
----------------	----------	----

TOTAL DE RELLENO	2,056.00	M3
------------------	----------	----

RECONSTRUCCION DE BORDO DE OBRAS DE PROTECCION

MARGEN DERECHA DEL RIO BLANCO, TRAMO 2,

SECTOR CAMPO OLIVO - BEJUCO

JURISDICCION DE POTRERILLOS

CORTE DE MEANDRO

EST.	AREA	VOLUMEN	VOL. ACUM
KMS	M2	M3	M3
0+010.00	2.57	0.00	0.00
0+020.00	5.33	39.50	39.50
0+030.00	8.13	67.30	106.80
0+040.00	9.19	86.60	193.40
0+050.00	9.09	91.40	284.80
0+060.00	8.76	89.25	374.05
0+070.00	4.14	64.50	438.55
0+080.00	1.15	26.45	465.00
CORTE		465.00	M3