

PROYECTO : RETIRO DE BORDO M.ARGEN DERECHA DEL RIO ULUA, SECTOR MEROA RIO .

JURISDICCION DE TELA, DEPTO. DE ATLANTIDA

TALUDES: 1.5: 1

CORONA: 4.00 mts

EST.	ELEVACIONES			CORTE (Mat. Existente)		RELLENO		
	T.N.	RAS.	ALTURA	AREA	VOLUMEN	AREA	VOLUMEN	VOLUMEN
KMS	MTS	MTS	MTS	M2	M3	M2	M3	M3
0+00.00	102.13	105.00	2.87	49.07	0.00	44.77	0.00	0.00
0+020.00	99.66	105.00	5.35	36.61	856.80	74.79	1,195.64	1,195.64
0+040.00	100.05	105.00	4.95	44.95	815.60	71.74	1,465.32	2,660.96
0+060.00	100.19	105.00	4.81	32.78	777.30	66.59	1,383.26	4,044.22
0+080.00	100.31	105.00	4.69	32.74	655.20	67.23	1,338.14	5,382.36
0+100.00	100.03	105.00	4.97	36.65	693.90	71.33	1,385.56	6,767.92
0+120.00	100.04	105.00	4.96	32.20	688.50	77.20	1,485.26	8,253.18
0+140.00	100.37	105.00	4.63	37.78	699.80	60.14	1,373.38	9,626.56
0+160.00	100.36	105.00	4.64	34.24	720.20	69.74	1,298.76	10,925.32
0+180.00	100.14	105.00	4.86	35.43	696.70	70.81	1,405.42	12,330.74
0+200.00	100.11	105.00	4.90	29.17	646.00	68.36	1,391.60	13,722.34
0+220.00	100.04	105.00	4.96	41.35	705.20	70.59	1,389.41	15,111.75
0+240.00	101.60	105.00	3.40	54.57	959.20	51.98	1,225.69	16,337.44
0+260.00	102.51	105.00	2.49	69.48	1,240.50	54.28	1,062.59	17,400.03
0+280.00	102.80	105.00	2.21	54.94	1,244.20	38.98	932.57	18,332.60
0+300.00	101.51	105.00	3.49	57.03	1,119.70	49.91	888.92	19,221.52
0+320.00	102.80	105.00	2.20	59.47	1,165.00	36.32	862.35	20,083.87
0+340.00	102.28	105.00	2.72	62.35	1,218.20	50.63	869.57	20,953.44
0+360.00	105.03	105.00	-0.03	23.18	855.30	11.15	617.87	21,571.31
0+380.00	105.16			0.00	0.00	10.00	211.54	21,782.85
0+400.00	105.14			0.00	0.00	10.00	200.00	21,982.85

15,757.30	Vol. Bordo =	21,983.00	m3
	Vol. De Corte =	15,757.00	m3
	Vol. Acarreado	6,226.00	m3