

PROYECTO : Construccion de Escollera de Piedra, margen Derecha del Rio Chamelecon,
 Colonia los Pinos - Puente la Ica.

Jurisdiccion de la Lima , Depto. De Cortes

VOLUMEN ESCOLLERA DE PIEDRA

CORONA PROM.: 3.00 mts

Talud: 1.5/1

EST. KMS	ELEVACION ESCOLLERA			AREA	VOLUMEN	VOLUMEN
	RAS.	FONDO PROM.	DIF. ELEV.	M2	M3	M3
0+320.00	29.00	21.50	7.50	36.82	0.00	0.00
0+340.00	29.00	21.50	7.50	47.50	843.20	843.20
0+360.00	29.00	21.50	7.50	45.61	931.10	1,774.30
0+380.00	29.00	21.50	7.50	39.81	854.20	2,628.50
0+400.00	29.00	21.50	7.50	40.77	805.80	3,434.30
0+420.00	29.00	21.50	7.50	33.10	738.70	4,173.00
0+440.00	29.00	21.50	7.50	39.18	722.80	4,895.80
0+460.00	29.00	21.50	7.50	34.00	731.80	5,627.60
0+480.00	29.00	21.50	7.50	31.73	657.30	6,284.90
0+500.00	29.00	21.50	7.50	29.40	611.30	6,896.20

PIEDRA :	6,896.20	M3
----------	----------	----