

			CORTE		SOBRELEVACION		RECONSTRUCCION , BORDO			CORTE		
EST.	ELEVACIONES		AREA	VOL.	AREA	VOL.	AREA	VOL.	VOL. ACUM	AREA	VOL.	VOL. ACUM
KMS	INV.	RAS.	M2	M3	M2	M3	M2	M3	M3	M2	M3	M3
0+000	98.60	101.00	5.45	0.00	6.14	0.00	11.59	0.00	0.00	0+120	17.13	0.00
0+040	98.60	101.00	3.74	91.86	15.18	256.69	18.92	348.54	348.54	0+140	17.13	342.54
0+060	98.60	101.00	2.59	63.26	21.52	366.96	24.11	430.22	778.76	0+160	15.82	329.50
0+080	98.60	101.00	0.94	35.29	21.42	429.40	22.36	464.69	1,243.45	0+180	16.29	321.11
0+100	98.60	101.00	0.73	16.71	24.63	460.50	25.36	477.22	1,720.67	0+200	14.89	311.78
0+120	98.60	101.00	0.71	14.42	25.47	500.96	26.18	515.38	2,236.05	0+220	22.46	373.49
0+140	98.60	101.00	1.01	17.23	18.82	442.87	19.83	460.10	2,696.15	0+240	29.51	519.74
0+160	98.60	101.00	1.73	27.38	21.77	405.83	23.49	433.21	3,129.36	0+260	25.10	546.19
0+180	98.60	101.00	1.32	30.48	26.30	480.66	27.62	511.13	3,640.49	0+280	17.07	421.78
0+200	98.60	101.00	0.68	20.05	26.90	532.03	27.59	552.08	4,192.57	0+300	14.56	316.31
0+220	98.60	101.00	0.47	11.55	24.14	510.42	24.61	521.97	4,714.54	0+320	14.88	294.34
0+240	98.60	101.00	0.57	10.36	24.59	487.33	25.16	497.69	5,212.23	0+340	20.88	357.56
0+260	98.60	101.00	0.82	13.84	23.79	483.84	24.61	497.68	5,709.91	0+360	27.42	482.99
0+280	98.60	101.00	1.19	20.09	23.76	475.46	24.95	495.55	6,205.46	0+380	14.29	417.12
0+300	98.60	101.00	1.61	28.00	25.14	488.92	26.75	516.92	6,722.38	0+400	15.76	300.54
0+320	98.60	101.00	0.75	23.61	27.04	521.80	27.79	545.41	7,267.79			
0+340	94.15	101.00	0.15	8.98	31.33	583.77	31.48	592.75	7,860.54			5,335.00
0+360	94.15	101.00	0.00	1.48	29.82	611.50	29.82	612.98	8,473.51			
0+380	94.15	101.00	77.06	770.55	26.76	565.76	103.81	1,336.32	9,809.83			
0+400	94.15	101.00	78.89	1,559.46	23.86	506.14	102.75	2,065.59	11,875.42			
0+420	94.15	101.00	82.72	1,616.13	22.36	462.10	105.08	2,078.22	13,953.65			
0+440	98.60	101.00	82.49	1,652.11	25.50	478.56	107.99	2,130.68	16,084.32			
0+460	98.60	101.00	0.84	833.25	26.28	517.86	27.12	1,351.11	17,435.43			
0+480	98.60	101.00	0.38	12.16	21.92	482.01	22.30	494.17	17,929.60			
0+500	98.60	101.00	0.32	6.98	22.03	439.41	22.34	446.40	18,376.00			
0+520	98.60	101.00	0.50	8.16	21.67	436.98	22.17	445.14	18,821.14			
0+540	94.50	101.00	0.68	11.75	21.35	430.19	22.02	441.94	19,263.08			
0+560	95.60	101.00	73.99	746.66	18.44	397.90	92.43	1,144.56	20,407.64			
0+580	98.60	101.00	77.50	1,514.86	19.84	382.84	97.34	1,897.71	22,305.35			
0+600	98.60	101.00	1.11	786.32	18.38	382.33	19.48	1,168.65	23,474.00			
							CORTE		9,953.00	M3		
							SOBRELEVACION		13,521.00	M3		
							VOL. TOTAL		23,474.00	M3		
							CANAL NUEVO		5,335.00	M3		