

**CIERRE BOQUETE Y SOBREVOLACION DE BORDO, MARGEN DERECHA
CANA ESTERO DE INDI0 - CONTRABORDO LOS CATRACHOS**

TALUD IZQ. : 2: 1

CORONA : 4.00 mts

TALUD DERE.. : 2:1

CODIGO: T1

EST.	AREA	VOLUMEN	VOL. ACUM
KMS	M2	M3	M3
0+00.00	7.517	0	0.00
0+010.00	7.762	76.395	76.40
0+020.00	8.496	81.29	157.69
0+030.00	9.266	88.81	246.50
0+040.00	9.942	96.04	342.54
0+050.00	48.154	290.48	633.02
0+060.00	50.095	491.245	1,124.26
0+070.00	53.763	519.29	1,643.55
0+080.00	50.704	522.335	2,165.89
0+090.00	45.122	479.13	2,645.02
0+100.00	49.204	471.63	3,116.65
0+110.00	53.017	511.105	3,627.75
0+120.00	52.265	526.41	4,154.16
0+130.00	45.337	488.01	4,642.17
0+140.00	44.817	450.77	5,092.94
0+150.00	45.521	451.69	5,544.63
0+160.00	48.218	468.695	6,013.33
0+170.00	45.855	470.365	6,483.69
0+180.00	52.265	490.6	6,974.29
0+190.00	43.429	478.47	7,452.76
0+200.00	44.551	439.9	7,892.66
0+210.00	47.882	462.165	8,354.83
0+220.00	22.481	351.815	8,706.64
0+230.00	22.3	223.905	8,930.55
0+240.00	19.4	208.5	9,139.05
0+250.00	15.702	175.51	9,314.56
0+260.00	15.954	158.28	9,472.84
0+270.00	16.362	161.58	9,634.42
0+280.00	19.102	177.32	9,811.74
0+290.00	18.555	188.285	10,000.02
0+300.00	19.569	190.62	10,190.64
0+310.00	21.845	207.07	10,397.71
0+320.00	20.348	210.965	10,608.68
0+330.00	18.654	195.01	10,803.69

0+340.00	21.975	203.145	11,006.83
0+350.00	25.209	235.92	11,242.75
0+360.00	22.246	237.275	11,480.03
0+370.00	21.362	218.04	11,698.07
0+380.00	25.413	233.875	11,931.94
0+390.00	30.38	278.965	12,210.91
0+400.00	32.211	312.955	12,523.86
0+410.00	32.039	321.25	12,845.11
0+420.00	39.922	359.805	13,204.92
0+430.00	45.889	429.055	13,633.97
0+440.00	22.318	341.034	13,975.00

VOL. RELLENO	13,975.00	M3
--------------	-----------	----

**CIERRE BOQUETE Y SOBREVACION DE BORDO, MARGEN DERECHA
CANA ESTERO DE INDI0 - CONTRABORDO LOS CATRACHOS**

TALUD IZQ. : 2: 1

CORONA : 4.00 mts

TALUD DERE.. : 2:1

CODIGO: T2

EST.	AREA	VOLUMEN	VOL. ACUM
KMS	M2	M3	M3
0+00.00	2.66	0.00	0.00
0+010.00	17.17	99.18	99.18
0+020.00	35.22	261.94	361.12
0+030.00	17.59	264.01	625.13
0+040.00	21.06	193.23	818.36
0+050.00	28.19	246.27	1,064.62
0+060.00	26.33	272.63	1,337.25
0+070.00	29.51	279.21	1,616.46
0+080.00	29.51	294.54	1,911.00

VOL. RELLENO	1,911.00	M3
--------------	----------	----

**CIERRE BOQUETE Y SOBREVACION DE BORDO, MARGEN DERECHA CANA
ESTERO DE INDIO - CONTRABORDO LOS CATRACHOS**

CONSTRUCCION DE BORDO

TALUD IZQ. : 2: 1

CORONA : 4.00 mts

TALUD DERE.. : 2:1

CODIGO: T3

EST.	INV.	RAS.	ALT.	AREA	VOL.	VOL. ACU.
KMS	Mts	Mts	Mts	M2	M3	M3
0+000.000	101.50	103.50	2.00	16.00	0.00	0.00
0+020.000	101.50	103.50	2.00	16.00	320.00	320.00
0+040.000	101.50	103.50	2.00	16.00	320.00	640.00
0+060.000	101.50	103.50	2.00	16.00	320.00	960.00
0+080.000	101.50	103.50	2.00	16.00	320.00	1,280.00
0+100.000	101.50	103.50	2.00	16.00	320.00	1,600.00
0+120.000	101.50	103.50	2.00	16.00	320.00	1,920.00
0+140.000	101.50	103.50	2.00	16.00	320.00	2,240.00
0+160.000	101.50	103.50	2.00	16.00	320.00	2,560.00
0+180.000	101.50	103.50	2.00	16.00	320.00	2,880.00
0+200.000	101.50	103.50	2.00	16.00	320.00	3,200.00
0+220.000	101.50	103.50	2.00	16.00	320.00	3,520.00
0+240.000	101.50	103.50	2.00	16.00	320.00	3,840.00

RELLENO =	3,840.00	M3
-----------	----------	----

**CIERRE BOQUETE Y SOBREVACION DE BORDO, MARGEN DERECHA CANA
ESTERO DE INDIO - CONTRABORDO LOS CATRACHOS**

CONSTRUCCION DE BORDO

TALUD IZQ. : 2: 1

CORONA : 4.00 mts

TALUD DERE.. : 2:1

CODIGO: T4

EST.	INV.	RAS.	ALT.	AREA	VOL.	VOL. ACU.
KMS	Mts	Mts	Mts	M2	M3	M3
0+000.000	101.50	103.50	2.00	16.00	0.00	0.00
0+020.000	101.50	103.50	2.00	16.00	320.00	320.00
0+040.000	101.50	103.50	2.00	16.00	320.00	640.00

RELLENO =	640.00	M3
-----------	--------	----