

**OBRA DE PROTECCION EN MARGEN IZQUIERDA DEL
RIO ULUA, SECTOR OMONITA**

CORONA: 4.00 TALUD : 1.5 /1

Rasante (Piedra) = 26.00 m.

EST.	AREA	VOLUMEN	VOLUMEN
KMS	M2	M3	M3
0+00.00	41.630	0.00	0.00
0+020.00	39.970	816.00	816.00
0+040.00	36.750	767.20	1,583.20
0+047.76	38.740	292.90	1,876.10
0+060.00	35.020	451.41	2,327.51
0+080.00	45.240	802.60	3,130.11
0+080.35	36.380	14.28	3,144.40
0+100.00	35.120	702.49	3,846.88
0+108.41	36.780	302.34	4,149.22
0+120.00	48.550	494.49	4,643.71
0+127.89	57.370	417.85	5,061.56
0+140.00	36.240	566.81	5,628.37
0+160.00	67.770	1,040.10	6,668.47
0+171.81	88.980	925.61	7,594.08
0+180.00	79.690	690.70	8,284.79
0+199.02	47.710	1,211.57	9,496.36
0+200.00	55.370	50.51	9,546.87
0+220.00	60.540	1,159.10	10,705.97
0+240.00	51.210	1,117.50	11,823.47
0+244.89	54.770	259.12	12,082.59
0+260.00	51.110	799.92	12,882.51
0+275.14	51.520	776.91	13,659.42
0+280.00	53.720	255.73	13,915.16
0+300.00	50.760	1,044.80	14,959.96
0+314.27	68.810	853.13	15,813.09
0+320.00	86.640	445.36	16,258.45
0+340.00	85.940	1,725.80	17,984.25
0+344.51	63.210	336.33	18,320.59
0+365.00	82.310	1,490.85	19,811.44
0+380.00	85.090	1,255.50	21,066.94
0+400.00	73.720	1,588.10	22,655.04
0+420.00	77.910	1,516.30	24,171.34
0+440.00	77.990	1,559.00	25,730.34
0+465.00	79.583	1,969.66	27,700.00
		27,700.00	