

**PROYECTO : RECONSTRUCCION DE BORDO Y CIERRE DE BOQUETE EN  
CONTRABORDO Y BRDO DE LA MARGEN DERECA DEL CANAL EL 32, SECTOR  
LAS TOMASAS  
JURISDICCION DE TELA, DEPARTAMENTO DE ATLANTIDA**

TALUDES : 2: 1

CORONA: 4.00 MTS

ESTACION	RASANTE	ZONA DE RELLENO		
		AREA DE RELLENO	VOL. RELLENO	VOL. ACUM. RELLENO
0+000	100.03	0.00	0.00	
0+020	100.00	19.40	193.98	193.98
0+040	99.98	61.10	630.44	824.42
0+060	99.95	36.95	430.58	1,255.00
0+080	99.93	6.69	103.86	1,358.86
0+100	99.90	3.78	44.49	1,403.35
0+120	99.88	1.93	23.04	1,426.39
0+140	99.85	95.01	952.06	2,378.45
0+160	99.83	102.61	1,121.15	3,499.60
0+180	99.80	97.37	1,076.34	4,575.94
0+200	99.78	36.94	466.80	5,042.75
0+220	99.75	0.65	43.48	5,086.23
0+240	99.73	1.06	11.24	5,097.47
0+260	99.71	1.65	17.58	5,115.05
0+280	99.68	2.58	27.46	5,142.52
0+300	99.66	3.95	42.08	5,184.60
0+320	99.63	5.36	57.52	5,242.12
0+340	99.61	7.10	76.33	5,318.44
0+360	99.58	9.02	97.25	5,415.69
0+380	99.56	11.40	123.06	5,538.75
0+400	99.53	34.06	352.25	5,891.00
			<b>VOLUMEN TOTAL DE RELLENO</b>	<b>5,891.00</b>

**PROYECTO : RECONSTRUCCION DE BORDO Y CIERRE DE  
BOQUETE EN CONTRABORDO Y BRDO DE LA MARGEN DERECA  
DEL CANAL EL 32, SECTOR LAS TOMASAS**

**JURISDICCION DE TELA, DEPARTAMENTO DE ATLANTIDA**

TALUDES : 2: 1

CORONA: 4.00 MTS

ESTACION	RASANTE	RELLENO		
		AREA DE RELLENO	VOL. RELLENO	VOL. ACUM. RELLENO
0+000	100.89	0.49	0.00	0.00
0+020	100.87	1.73	17.74	17.74
0+040	100.84	10.12	102.90	120.63
0+060	100.82	15.33	163.45	284.08
0+080	100.79	17.55	190.81	474.89
0+100	100.77	19.65	214.02	688.91
0+120	100.74	128.86	1,308.22	1,997.13
0+140	100.72	129.40	1,422.84	3,419.97
0+160	100.69	123.77	1,367.07	4,787.03
0+180	100.67	135.98	1,483.55	6,270.58
0+200	100.64	124.62	1,382.17	7,652.75
0+220	100.62	14.97	274.31	7,927.06
0+240	100.59	17.87	193.63	8,120.69
0+260	100.57	25.22	270.06	8,390.74
0+280	100.55	22.10	246.21	8,636.95
0+300	100.52	15.76	179.67	8,816.62
0+320	100.50	16.06	176.39	8,993.01
0+340	100.47	15.93	175.38	9,168.39
0+360	100.45	14.96	165.51	9,333.90
0+380	100.42	24.34	258.37	9,592.27
0+400	100.40	18.34	207.74	9,800.01
0+420	100.37	14.81	166.44	9,966.45
0+440	100.35	14.40	158.82	10,125.27
0+460	100.32	9.55	109.87	10,235.14
0+480	100.30	14.46	154.13	10,389.27
0+500	100.28	17.58	190.30	10,579.57
0+520	100.25	12.52	142.74	10,722.31
0+540	100.23	133.65	1,349.03	12,071.34
0+560	100.20	222.34	2,357.04	14,428.38
0+580	100.18	227.48	2,497.13	16,925.51
0+600	100.15	109.06	1,318.12	18,243.63
0+620	100.13	97.12	1,080.22	19,323.85
0+640	100.10	17.47	271.86	19,595.71

**PROYECTO : RECONSTRUCCION DE BORDO Y CIERRE DE  
BOQUETE EN CONTRABORDO Y BRDO DE LA MARGEN DERECA  
DEL CANAL EL 32, SECTOR LAS TOMASAS**

**JURISDICCION DE TELA, DEPARTAMENTO DE ATLANTIDA**

TALUDES : 2: 1

CORONA: 4.00 MTS

ESTACION	RASANTE	RELLENO		
		AREA DE RELLENO	VOL. RELLENO	VOL. ACUM. RELLENO
0+660	100.08	40.03	417.75	20,013.46
0+680	100.05	17.31	213.16	20,226.62
0+700	100.03	13.57	152.99	20,379.61
0+720	100.00	15.02	163.77	20,543.38
0+740	99.98	12.13	136.29	20,679.67
0+760	99.96	10.28	114.97	20,794.64
0+780	99.93	107.46	1,084.88	21,879.52
0+800	99.91	80.01	907.51	22,787.03
0+820	99.88	105.01	1,130.10	23,917.13
0+840	99.86	1.87	123.70	24,040.82
0+860	99.83	2.29	24.76	24,065.58
0+880	99.81	2.72	29.46	24,095.04
0+900	99.78	5.32	55.65	24,150.69
0+920	99.76	0.00	5.31	24,156.00
0+940	99.73	0.00	0.00	24,156.00
0+960	99.71	0.00	0.00	24,156.00
0+963	99.68	0.00	0.00	24,156.00
		<b>VOLUMEN TOTAL DE RELLENO</b>		<b>24,156.00</b>